

SECTION 311200 – EARTHWORK

PART 1 - GENERAL

- 1.1 Any deviances from the following instructions must be approved during design by WVU Facilities Management Personnel.
- 1.2 Performance Requirements
- A. The contractor shall be responsible for satisfying any and all erosion and sediment control measures necessary on the project site.
 - B. The contractor shall be responsible for obtaining any local grading permits.
 - C. Title 47 of the Division of Environmental Protection, Office of Water Resources (NPDES) shall be followed. All fees associated with permitting shall be considered part of the design fee.
 - D. All topsoil stripped from the site shall remain the property of West Virginia University unless otherwise directed.
 - E. All stockpile locations shall be approved by West Virginia University.
 - F. Burning is prohibited on West Virginia University Property.
 - G. Blasting is prohibited on West Virginia University Property unless otherwise directed.
 - H. All waste materials and materials unsuitable for fill or use shall be removed from the property and disposed of in accordance with all state, federal and local laws.
 - I. Prior to excavation and placement of fill the contractor/consultant shall contact Miss Utility or similar agency to locate known utilities in the project area.
 - J. Prior to excavation and placement of fill the contractor/consultant shall contact West Virginia University to review know utility drawings for the area.
 - K. Do not interrupt existing utility services without permission from West Virginia University.
 - L. The contractor shall install and maintain a construction entrance to the project, which will not track materials or debris onto adjoining roadways or facilities.
 - M. The contractor shall employ a qualified independent geotechnical/materials testing laboratory to provide materials testing and inspection services during earthwork operations. Copies of all reports, inspections and test will be forwarded to West Virginia University.

WVU DESIGN GUIDELINES & CONSTRUCTION STANDARDS
DIVISION 31 – EARTHWORK

PART 2 - **PRODUCTS** - Not Used

PART 3 - EXECUTION

3.1 Installation

A. Compaction requirements:

Under structures, steps and pavements	Top 12 inches @ 100% remaining @ 95%
Lawn or unpaved areas	90%
Walkways	95%

END OF SECTION 02300