WVU DESIGN GUIDELINES & CONSTRUCTION STANDARDS DIVISION 28 – ELECTRONIC SAFETY AND SECURITY

SECTION 282500 - ELECTRONIC CARD ACCESS CONTROL SYSTEM/SPECIFICATIONS

PART 1 - GENERAL

1.1 This document is the General Design Guidelines and Specifications for the WVU Electronic Card Access Control System. It is intended to address issues that relate directly to access control installations.

A. Introduction

The WVU card access system for electronic locks is a one card system by CBord called CS Gold that is on track 2 of the University ID card. These are Magnetic stripe cards. WVU also utilizes a stand-alone card system by Onity that operates on the same card on track 3. These systems are under the administration of Mountaineer Card Office.

B. Qualifications

- 1. All General Contractors and their subcontractors working on campus shall meet the following qualifications at a local level and must submit evidence accordingly. The General Contractor shall have:
 - A. Licensed Electricians to install all the CBord equipment, conduit, power supplies, and work boxes with terminal strips. Photocopy of license shall be submitted with response package.
 - B. Certified/Licensed Low Voltage Electricians working with low voltage to pull wires and make all final connections. Photocopies shall be submitted with response package as proof of Certification/Licensing. The following are accepted by WVU as proof:
 - Copy of Company certificate stating Low Voltage Electrician being certified,
 - Copy of West Virginia State license in Low Voltage, or
 - Documentation of training course completion

C. General Requirements and Notes

- 1. WVU has obtained and installed the CBord server software, database and licensing exclusively. The University has completed installation of door access hardware components at existing campus locations. The CBord system has been established in a decentralized manner where the departments administrate and monitor assets that they own and the database/server/software configuration are administrated centrally in the Mountaineer Card Office. The WVU Mountaineer Card Office and WVU Facilities Management Lock Shop will have final approval of door hardware, wiring, and electronic devices/controllers used in construction where work has been subcontracted to 3rd parties. Mountaineer Card Office will specify what CBord equipment is used. It is the intent of WVU to empower General Contractors or Subcontractors to have primary responsibility of access control installations in accordance with these specifications and guidelines.
- 2. It is the responsibility of the bidder/General Contractor to generate an equivalent equipment list prior to bidding or installation that denotes exceptions taken with door hardware schedules, components or designs being used which may hamper their ability to provide a secure and compliant access control product.
- 3. WVU Mountaineer Card Office, Facilities Planning, Design & Construction Services, General Contractor, and the Architect will review designs for access control on new construction and existing structures.

- 4. A final door walkthrough will take place with the general contractor, Mountaineer Card Office and Lock Shop representative, project managers and customer prior to acceptance of any access control work. All doors must be functioning properly in the field as well as within the access control software.
- 5. Coordination and hardware review meetings will be setup by the design firm, between the WVU Mountaineer Card Office, Lock Shop representative, the door hardware consultant and the access control designer prior to bidding of projects.
- 6. WVU Facilities Management Lock Shop and WVU Mountaineer Card Office shall review all submittals related to electronic card access system in conjunction with the architect.
- 7. Electronic card access control system shall be utilized on all exterior doors, data closets, main janitorial support area, mechanical rooms (rooms that contain Air Handling Units, Pumps, Boilers, etc.), and mechanical penthouse for new construction and major renovation projects.
- 8. WVU requires at a minimum that all exterior doors be prepped with card access or electronic door position monitoring.
- 9. All locks must be keyed into the University existing Great, Great Grand Master key system and WVU Lock Shop will provide this information.
- 10. Consider prepping for Video Surveillance System by running conduit and placing junction boxes for future camera installation. The Department of Public Safety (DPS) is responsible for assessing and approving the locations of all access control devices. DPS determines the feasibility of the location of equipment and advises on the needs related to equipment. DPS is responsible for monitoring and responding to all University access control and security issues. DPS reviews all phases of the access control documentation for compliance with device locations and standard equipment.
- 11. Project Manager will make a request for temporary consultant contractor ID card from WVU Mountaineer Card Office. Contractor will go to Mountaineer Card Office to take his/her picture and obtain temporary ID card.

D. Base Specifications

- 1. The system shall fully and completely integrate with the WVU's door access system purchased from CBord.
- 2. Allow proper egress in emergency situations such that no special knowledge or card is required to exit a space.
- 3. Must comply with WVU ADA standards.
- 4. All hardware mounted in exterior locations shall be weather resistant and designed to maintain the aesthetic beauty of the campus. The finish of the access control hardware should match the finish of the other door hardware.
- 5. Hardware must be durable enough to withstand high traffic locations without frequent failure.
- 6. All 24V wiring runs for CBord and locking equipment shall be no more than 200 feet.
- 7. All data wiring runs from CBord to the door shall be no more than 2000 feet.
- 8. All aluminum door stiles shall be 5" wide.
- 9. Run data lines and electrical wires in separate conduit.
- 10. Upon finishing the job, the General Contractor should properly label panel boards marking what power supply and locks it controls.
- 11. Upon finishing the job, the General Contractor should properly label the power supply for locks marking which room it controls.

12. Follow manufacturer's installation guidelines.

1.2 Reference Standard

• Finish Hardware- Division 08, Section 087100

PART 2 - PRODUCTS

- A. WVU Online and Offline Locks
 - 1. WVU uses the following online locks for securing outside and inside doors
 - a. Exit devices (panic bars) Rim type devices
 - b. Mortise locks
 - c. Cylindrical locks
 - d. Magnetic Locks (retrofitting only)
 - e. Electric Strikes (retrofitting only)
 - 2. WVU uses the following locks for stand-alone offline locks
 - a. Onity mortise lock
 - b. Onity cylindrical lock
 - c. Onity door unit that is used in conjunction with electrified locks (this must include an Onity power supply with all options).
 - d. Magnetic Locks (retrofitting only)
 - e. Electric Strike (retrofitting only)
- B. Door Locks & CBord Standardized Hardware
 - The following hardware is the required hardware for access control integrations.
 These are commonly used and stocked by the University Warehouse for the campus maintenance contract. Door and locking hardware substitutions for CBord will be brought to the attention of the Mountaineer Card Office and Lock Shop for approval.
 - A. Controllers: CBord Components

V-1000

V-100

V-200

V-300

RS485 PIM

RS485 Hub

B. Readers: CBord

BR-20

A-2005

MR-5/MR-20

AD300/AD400

- C. Lock Manufacturers
 - A. Panic Bars
 - a. Von Duprin 98/99 Series
 - b. Sargent 8800/8888 Series
 - B. Mortise Locks
 - a. Sargent 80 Series
 - b. Schlage L Series
 - C. Cylindrical Locks
 - a. Sargent 10 Line
 - b. Schlage D Series
- D. Locks: The following are WVU standard locks used in online card swipe locks. All locks are 24 V, US26D is the standard finish. All locks and cylinders must accept

Best 7 pin cores TB keyway. All locks must meet all codes for the opening. All locks must have RX & LX options.

- A. Panic bars & trims
 - a. Sargent 8800/8888 series with ETJ trim
 - b. Von Duprin 99 with #03 lever
- B. Mortise locks
 - a. Sargent 8200 series with LNJ trim
 - b. Schlage L series with #03 trim
- C. Cylindrical locks
 - a. Sargent 10 line with LNJ lever
 - b. Schlage D series with TRL lever
- E. All locks and locking devices must have request to Exit (REX). REX switches will be built-in to locking devices and door locking hardware on all new construction and when possible on existing structures. If REX switches are not built into lock, surface mount Bosch #DS 150i REX.
- F. Electric Strikes: This option is used only in retrofitting situations and not in new construction.
 - A. Sargent HES 9500 LBSM Series for Panic Bars
 - B. Strikes for Mortise (1006 LBSM Series) and Cylindrical Locks (7000 or 7500 LBSM Series).
 - C. Magnetic Locks: all Magnetic Locks should be Schlage and must have Magnetic Bond Sensor (MBS), Door Position Sensor (DPS), and Relock Time Delay (RTD).
- G. Electric Power Transfer
 - A. Securitron (Sargent) #cept-10
 - B. Von Duprin #EPT-2 or -10
 - C. Electrical Hinges must be 8 Wire hinge and used only in retrofitting situations
- H. Power Supplies and Batteries must be 7 Amperes
 - A. Power supply for locks only: perform calculations based on how many doors should be connected to a single power supply. It cannot max 60% of the power supply.
 - 1. Altronix # AL1012ULACMCB
 - 2. 7 hour battery backup
 - B. Altronix Batteries
 - 1. Altronix BT12/6 12VDC/7AH
 - 2. Altronix BT12/12 12VDC/12AH

www.altronix.com

- I. Power supply for locks only: perform calculations based on how many doors should be connected to a single power supply. It cannot max 60% of the power supply.
 - 3. Altronix # AL1024ULACMCB
 - 4. 7 hour battery backup
- J. Relays
 - A. Altronix Relay
 - 1. Altronix RB1224
 - 2. Altronix RBR 1224
 - www.altronix.com
- K. Closing Devices
 - A. LCN Closers
 - LCN Series surface mount closers 4040 Series http://www.lcnclosers.com

- 2. ADA closer low energy LCN 4600 series unless otherwise required by application
- B. Sargent 281 or 351 Series

L. Cabling

- A. Belden 6120 UL, 14 AWG
- B. Belden 6504 FE. 6 Conductors
- C. Belden 6400 FE, 2 Conductors
- D. Electrolynx QC-C300(All connections need to be company, plug-in, or tab connections)
- E. Electrolynx QC-C1500 (All connections need to be company, plug-in, or tab connections)
- M. Emergency Push Button Covers w/Horn (must have timer)
 - A. Safety Technology Incorporated (STI)
- N. Network Topography
 - 1. WVU uses a star configuration with each access/alarm point being a 'home run' back to the access control panel from the junction box located above the door. The cabling between the junction box and the access control panel will be the cabling outlined in the section 4.10. All communication and power to the individual doors will come from the access control panel location. An exception to this will be made when specific hardware requires a localized power supply. When possible a trunk conduit/raceway should be established in common hallways to accommodate multiple 'home run' composite cables.

PART 3 - EXECUTION

- A. Installation Requirements
 - 1. Controllers
 - A. Panel and any network device server will be wired through power supply with battery backup.
 - B. Power is to be hardwired to access control panels.
 - C. Access control panel and power supplies will be on isolated circuit (s).
 - D. Circuit from Fire Alarm panel to each access control panel.
 - E. Access control panels are to be installed in network or electrical closets that are between 42° and 120° F.
 - F. Each panel will be named according to the WVU Mountaineer Card posted outside the panel door.
 - G. Each panel will have a list of readers (university door numbers) connected to it located inside the panel.
 - H. Installation of network connection drop is to be coordinated through MCS Card Services. Drop termination is to be inside of access control panel to prevent tampering.
 - I. The MAC address and IP address for each panel/device will be posted on the outside panel door (Provided by MCS).
 - J. IP addressing information can be obtained by contacting the WVU Mountaineer Card Office.
 - K. All panel boxes are to have functioning locking hardware with keys. Keys will be submitted to the WVU Mountaineer Card Office upon completion of install
 - L. Necessary devices will be password protected.

M. All access control panels and unused conduit are to be removed prior to installation of new access control panel (s) (retrofitting only).

2. Wiring & Conduit

- A. All communication and power to the individual doors will come from the access control panel location. An exception to this will be made when specific hardware requires a localized power supply. When possible a trunk conduit/raceway should be established in common hallways to accommodate multiple 'home run' composite cables.
- B. All wiring run will 'home run' from door junction box to control panel location.
- C. Devices must be hardwired, with all wiring installed in conduit in accordance with National Electrical Code and written University standards for conduit and system installation for class 2 fire protection, signaling control devices.
- D. Wire connections to the access control panel are to be clearly labeled.
- E. Wiring which contacts metal edges will be buffered with bushings or rubber grommets to prevent damaged wires and shorts. Examples include wiring meeting conduit ends, panel and junction box holes.
- F. Conduit must be strapped within 24" of junction boxes.
- G. All junction boxes must be covered and contents labeled when appropriate (ex. Junction box with relay for handicap button).
- H. Junction boxes must match device being mounted.
- I. Both Setscrew conduit fitting and Compression fitting are allowed.
- J. Minimum conduit size is ¾ inch.
- K. Conduit can be 40% full of square inch capacity.
- L. The conduit system and cabling installed must be distinct and separate from the wire way/conduit system housing voice/data cables in campus buildings.
- M. Connections to devices must be secured, so that no cords may be easily disconnected from the devices and no cords are left exposed to unauthorized tampering.
- N. All low voltage wiring cable to be plenum rated, stranded, and color coded.
- O. Wire nuts are not permissible. WVU prefers Crimp connectors.
- P. Crimp connectors should be installed with appropriate crimping tools.
- Q. All wiring shall be installed in a protective housing such as conduit or wiremold.
- R. When necessary use cable ties to bundle cables.
- S. Use the attached wiring chart for ElectroLynx systems.

3. Door & Frame:

- A. Prepped door frames shall have continuous conduit from junction box above door frame to termination box in frame.
- 4. Header Mounted Door Position Switch:
 - A. Door switches will be flush mounted on the door header from the strike side of the doorframe approximately 4" from Jam.
 - B. Surface mount switches will have armored cable between the switch and the cable entrance hole in the door.
 - C. The holes for flush mounted door switches must be drilled the exact size for the switch being used. A tight friction fit must be achieved.

5. Door Hardware

- A. Door hardware will be fail-secure with mechanical manual egress from the secured side unless fire spec says it needs to be fail-safe.
- B. Door switching and power will reside in the access control panel location. In the case of an electrified exit device (such as a Von Duprin EL crashbar) power supply is to be located no more than 50 feet from door.

- C. Power supply will be connected to building emergency circuits when possible.
- D. Power supplies will have a 7amp hour battery backup or higher.
- E. Facilities Lock Shop and Mountaineer Card Office will be notified of location of power supplies when located away from access control panel via As-Built drawings.
- F. No more than 65% Amps in power supply with exit devices per independent 24v power supply.
- G. Request to exit switches will be built-in to exit devices and door locking hardware on all new construction and when possible on existing structures.
- H. Door hardware is to be set so that 'dogging' functionality is not possible.
- I. Door hardware will have key override and capable of accepting small Best format interchangeable core.
- J. Door hardware power supplies will have locking junction box.

6. Readers

- A. Door access readers must read an identifying number from the University ID card.
- B. The Mountaineer Card Office should be consulted during design to identify the appropriate type of readers used for the location. Readers will never hang or have overlapping edges from the device that they are mounted on.
- C. Handicap operators will be wired so that a valid card read enables push button. Multiple relays including a timer relay are required for this configuration (see diagram).
- D. If the card reader uses a RJ 11 termination, the cable run should be striped and terminated in RJ 11 connector per manufacturing instruction instead of using the enclosed pig-tail.

7. Plans


- A. Drawings and Specifications
 - 1. The Access Control System shall have dedicated detail drawings in Section E of the construction plans. The detail drawings shall include:
 - a. Control panel location
 - b. Security door matrix which includes door number, door size, hardware set/schedule, location, and drawing number.
 - c. Door detail and elevation for each security door (Examples are located in sections 7.3 & 7.4).

8. Process

A. WVU Mountaineer Card Office will be responsible for software programming. Programming work shall be coordinated with WVU Mountaineer Card Office in advance of project completion.

9. Building Requirements

A. Campus network is used for connectivity. WVU Mountaineer Card Office makes a request to Office of Information Technology (OIT) for several ports. OIT provides the right port and Contractor runs a patch cable from the port.





Typical WVU Access Control Panel Layout

DRAWING TITLE: ARCHITECTURAL PROJECT NAME: ADA BUTTON INT.	DRAWING NO. DRAWN BY: LIZA RIGUCCI	SCALE: NTS DATE: 11/18/2011
PROJECT NUMBER: PROJECT MANAGER: ZENABA QUADEER	BUILDING NAME: BUILDING NUMBER:	REVISION NO. 1 SHEET NO. 1 OF 5










NOTES:

1. This design is used when monitoring doors only. No electronic opening functionality

Single Door, Position Switch Only



NOTES:


1. This internal door design can be used on exiting construction when card access, remote unlocking or time schedules are needed. Door hardware is set so for manual mechanical egress from the secured side with locked handle on the unsecured side (lock will need modification to eliminate 'dogging' capability with key). Motion sensor generates request to exit. Areas with significant wind/buidling pressure and high traffic areas are not good candidates for PIR request to exits.

Single Door, Position Switch, Card In, Electrified

Strike with PIR Request to Exit


DRAWING TITLE: ARCHITECTURAL PROJECT NAME: ADA BUTTON INT.	DRAWING NO. DRAWN BY: LIZA RIGUCCI	SCALE: NTS DATE: 11/18/2011
PROJECT NUMBER: PROJECT MANAGER: ZENABA QUADEER	BUILDING NAME: BUILDING NUMBER:	REVISION NO. 1 SHEET NO. 2 OF 5





NOTES:

Single Door, Position Switch, Card In, Electrified Mortise Lockset with Built-In Request to Exit





Single Door, Position Switch, Card In, Electrified CrashBar Exit Device with Built-In Request to Exit

DRAWING TITLE: ARCHITECTURAL PROJECT NAME: ADA BUTTON INT.	DRAWING NO. DRAWN BY: LIZA RIGUCCI	SCALE: NTS DATE: 11/18/2011
PROJECT NUMBER: PROJECT MANAGER: ZENABA QUADEER	BUILDING NAME: BUILDING NUMBER:	REVISION NO. 1 SHEET NO. 3 OF 5









NOTES:

NUTES:


1. This Internal single door design should be used on new or existing construction. Boor hardware is set for manual mechanical egress from the secured side. Valid card read will enable tocked handle trin on the unsecured side (lock will not have 'doggling' capability with key). Request to exit is built-in to the locking hardware. The door will be cored between mortise lock and electric hinge/transfer.

Double Door, Mullion, Two Electrified Crash Bar, Built—In REX's ADA Door Operator

DRAWING TITLE:	ARCHITECTURAL	DRAWING NO.	_	SCALE:	NTS
PROJECT NAME:	ADA_BUTTON_INT.	DRAWN BY:	LIZA_RIGUCCI	DATE:	05/09/2012
PROJECT NUMBER:	_	BUILDING NAME:	_	REVISION	N NO. 1
PROJECT MANAGER	: ZENABA_QADEER	BUILDING NUMBER:	:_	SHEET NO	D. 4 OF 5







DRAWING TITLE: ARCHITECTURAL PROJECT NAME: ADA BUTTON INT.	DRAWING NO. DRAWN BY: LIZA RIGUCCI	SCALE: NTS DATE: 11/18/2011
PROJECT NUMBER: PROJECT MANAGER: ZENABA QUADEER	BUILDING NAME: BUILDING NUMBER:	REVISION NO. 1 SHEET NO. 5 OF 5


Wiring Chart

Use this chart to dertermine wiring assignment for each product (by wire color).

See legend on next page

ELECTROLYNX SYSTEM

PRODUCT	ELECT			NECTOR					4 PIN CO	ONNECTOR		F	LYING LEADS	
PRODUCT	1-Black 2-Red	3-White	4-Green	5-Orange	6-Blue	2 P	8-Yellow	9-Voilet	10-Gray	11-Pink	12-Tan	12-Red/Green	14-Red/Yellow	15-Red/Black
CYLINDRICAL LOCKS		3-Wnite				/-Brown	8- Tellow		10-Gray		12-1an	12-Red/Green		15-Red/Black
	POWER		SWITCH	[SWITCH		OPEN		SWITCH			SWITCH	
CORBIN RUSSWIN	12 or 24 V DC or AC													
	NEG POS													
SARGENT	24 V DC or AC NEG POS													
YALE	12 or 24 V DC or AC		REX - OPTION		ł									
	NEG POS	С	NO	NC										
MORTISE LOCKS														
CORBIN RUSSWIN	12 or 24 V DC or AC		M92 - OPTION	į.	M9	01 / M105 - OPTIO	N							
	NEG POS	С	NO	NC	С	NO	NC							
SARGENT	12 or 24 V DC or AC		X - PREFIX (CA			X - PREFIX (CAP)	_			LX/DX - PREFIX				
WALE 0000 C '	NEG POS	С	NO	NC	С	NO	NC		С	NO	NC			
YALE - 8800 Series	12 or 24 V DC or AC NEG POS	C	X - OPTION (C.	NC NC	c c	X - PREFIX (CAP)	NC		С	LBM/DBM - OPTION	NC			
ELECTRIFIED EXIT TRIM	NEG POS	·	NO	NC.	C	NO	NC.		C	NO	NC.			
CORBIN RUSSWIN	12 or 24 V DC or AC		M98 - OPTION											
	NEG POS	С	NO	NC										
SARGENT	12 or 24 V DC or AC		54 - PREFIX											
	NEG POS	С	NO	NC										
YALE	12 or 24 V DC or AC		SM - OPTION											
	NEG POS	С	NO	NC										
EXIT DEVICES	10		1401 -											
CORBIN RUSSWIN	12 or 24 V DC or AC SOL:/M94/M97 - OPTION	-	M91 - OPTION	•	1	M92 - OPTION			1	M93 - OPTION				
	SOL./M94/M97 - OPTION NEG POS	С	NO	NC	С	NO	NC		С	NO	NC			
SARGENT	24 V DC		53 - PREFIX	- AC			NC.	24 V D	C OR AC	NU	NC	 		
	56/58 - OPTION				ĺ	55 - PREFIX			PREFIX	1				
	NEG POS	С	NO	NC	С	NO	NC	NEG	POS	ĺ				
YALE	12 or 24 V DC or AC		S - OPTION			B - OPTION				0 - OPTION				
	SOL./P/G - OPTION													
	NEG POS	С	NO	NC	С	NO	NC		С	NO	NC			
ALARMED EXIT DEVICES CORBIN RUSSWIN M61 Alarm	9 V DC or AC					RM			MPER		SET			
CORBIN RUSSWIN M61 Alarm	9 V DC or AC	REX	EG	REX	M35	- HARDWIRED O	PTION	TAN	TPER	KE	SET			
	NEG POS	POS	EG	NEG	С	NO	NC	POS	NEG	POS	NEG			
SARGENT -AL-80 Series	9 V DC	REX	EG	REX		RM		I	DS	I	RR			
						6 KIT (HARDWIRI								
SARGENT -5100.5800	NEG POS 9 V DC	POS MS	EG	NEG	С	NO	NC	POS	NEG	POS	NEG			
DIROLIVI STOOLSOO	NEG POS	POS												
SARGENT -540.550	9 V DC	REMOTE MONI	TOR, DOOR STAT	US, REMOTE RESE	ET - FIELD SELECTED	,								
	NEG POS													
YALE	9 V DC or AC	REX	EG	REX	<u> </u>	RM			MPER	RE	SET			
	A - OPTION	POS	EG	NEG	С		HW - OPTIO	POS	NEG	POS	NEG			
DELAYED EGRESS EXIT	NEG POS	PUS	EG	NEG		NO	NC.	PUS	NEG	PUS	NEG			
DEVICES														
CORBIN RUSSWIN	12 or 24 V DC or AC	SECURI	E OUTPUT	ALARI	M OUTPUT	RESET	BYPASS							
	NEG POS	NO	NC	NO	NC	•	•							
SARGENT -57-80 Series	24 V DC	FA	EG	El	DS	EXTERNAL MAG	GNET							
	NEG POS		EG			•	•							
SARGENT -59-80 Series	24 V DC	FA	EG	El	DS		RAR			LBM - OPTION			OICE/GANG	
YALE	NEG POS 12 or 24 V DC or AC		EG OUTPUT		M OUTPUT	С	NO	NC	С	NO	NC	С	NO	NC
TALE		NC SECURI	E OUTPUT	NO NO	NOUTPUT	RESET	BYPASS							
ACCESS CONTROL DEVICES	NEG POS	M.	- 100	110	INC.									
CORBIN RUSSWIN - Access 800	9 V DC	REX	EG	REX	DATS IN	DATA OUT	RTS							
CADENTE CUR CLC.	NEG POS	POS	EG	NEG		•	•				1			
SARENT - G1 Profile Series	9 V DC	REX	EG	REX	1					DM	DM			
		l - PREFIX			1						11.5			
SARGENT- N1 Profile Series	NEG POS 12 or 24 V DC	POS	EG EG	NEG DPS INPUT	RS485 DATA-A	RS485 DATA-B	1			A	В			
SARGENT- INT PTOTHE SETIES	12 or 24 V DC NEG POS	LC C	EG EG	DPS INPUT	RS485 DATA-A	RS485 DATA-B								
YALE - eBOSS Cylindrical Lock	9 V DC or AC	Ť	REX - OPTION			E ENTRY						 		
	NEG POS	С	NO	NC	С	NO	ł							
YALE - eBOSS Mortise Lock	9 V DC or AC	Ť				E ENTRY						 		
	NEG POS	i			С	NO	1							
FOLGER ADAM EDC Products	12 or 24 V DC		SWITCH#1			SWITCH #2				SWITCH #3				
HES Products	NEG POS 12 or 24 V DC	С	NC SWITCH#1	NO	NO	C SWITCH #2	NC		NO	C SWITCH#3	NC	<u> </u>		
TILD FIUUUUS	NEG POS	С	NC/EG	NO	NO	C C	NC	1	NO	C C	NC	·		
SECURITRDN Products (Except	12 or 24 V DC		SWITCH#1			SWITCH #2		ALVING :		SWITCH#3		DANDS		
those listed below)		<u> </u>				SWITCH #2		24 V DC OR AC				24 V DC		
SECURITRON .SMC HANDLE EL-	NEG POS	С	NC/EG	NO	NO	С	NC	POS	NO	C	NC	NEG		
EMH Series	12 V DC		SWITCH #1		1									
	NEG POS	С	NC	NO	1									
SECURITRON -Touch Sense. EL-														
TSB-3 Series. EL-TSH Series	12 V DC	(NC	PAIR)	(NO	O PAIR)									
İ	NEG POS	NC	NC	NO	NO	<u> </u>		<u></u>						
SECURITRON- Power Transfer. EL-				Wire colors	will coordinate w	ith the ASSA AE	3LOY product	it's connected to						
SECURITRON- Power Transfer. EL- EPT. EL-EPTL				Wire colors	will coordinate w	vith the ASSA AI	BLOY product	it's connected to						



Door Security Solutions™

Wiring Chart

LEGEND

RR REMOTE RESET

NO	NORMALLY OPEN CONTACT	53	LATCHBOLT MONITOR
NC	NORMALLY CLOSED CONTACT	54	LEVER MONITOR
*	SINGLE INPUT CONTACT	55	REQUEST TO EXIT
		56	MOTORIZED LATCH RETRACTION
CORBIN RU	SSWIN	57	DELAYED EGRESS - EXTERNAL MAGNET
D	DELAYED EGRESS	58	ELECTRIC DOGGING
EG	EARTH GROUND	59	DELAYED EGRESS - ELECTROGUARD
M35	HARDWIRED	Α	SINGLE INPUT CONTACT
M61	ALARM EXIT	В	SINGLE INPUT CONTACT
M91	LATCHBOLT MONITOR	OPS	DOOR POSITION CONTACT
M92	TOUCH BAR MONITOR/REQUEST TO EXIT	OS	DOOR STATUS
M93	OUTSIDE TRIM MONITOR	OM	DOOR MONITOR
M94	ELECTRIC LATCH PULLBACK	OX	DEADBOLT MONITOR
M97		EG	EARTH GROUND
M98	SECURITY MONITOR (EXIT TRIM)		EXTERNAL INHIBIT CONTACT
M105	SECURITY MONITOR (MORTISE LOCK)	FA	FIRE ALARM CONTACT
REX	REQUEST TO EXIT	LC	LOOP COMMON
RM	REMOTE MONITOR	LX or LBM	LATCHBOLT MONITOR
		MS	MONITOR SIGNAL
		RX or REX	REQUEST TO EXIT
		RM	REMOTE MONITOR
		RAR	REMOTE ALARM RELAY

SARGENT

YALF

1 / \	
Α	HARDWIRED - POWER
В	TOUCH BAR MONITOR
OMB	DEADBOLT MONITOR
HW	HARDWIRED
LBM	LATCHBOLT MONITOR
0	OUTSIDE TRIM MONITO
REX	REQUEST TO EXIT
RM	REMOTE MONITOR
SM	SECURITY MONITOR
S	BOLT POSITION MONITO

This information 1s current as of printing (May 2006). Please contact your local Door Security SolutiOns representative or the manufacturer for specific technical questions.

Door Security Solutions'"

110 Sargent Drive

New Haven. CT 06511

800.DSS.EZ4U (377.3948) | 203.624.5225

c COMMON CONTACT

www.assaabloydss.com

An ASSA ABLOY Group company

©ASSA ABLOY SALES & MARKETING GROUP INC. 2005. 2006

2350-008-5/06

Architectural & Electromechanical Hardware Doors & Frames

CORBIN RUSSWIN FOLGER ADAM EDC HES McKINNEY RIXSON SARGENT SECURITRON YALE CECO DOOR CURRIES FLEMING GRAHAM

ASSAABLOY